

BANGALORE DIVISION.

The 28th December 1897.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Bangalore division, up to 15th January 1898, for constructing a Cottage Hospital at the Palace Compound, Bangalore. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of December 1898.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's office at Bangalore between the hours of 12 A. M. and 4 P. M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer and accompanied by a statement, in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 200 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for constructing a Cottage Hospital at the Palace Compound, Bangalore;" in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Chief Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Constructing a Cottage Hospital in the Palace Compound in Bangalore.

Items.	Per.	Rate.	Quantity.	Cost.
		Rs. a. p.		
Earthwork excavation and filling in basement	...	Cyd.	595	
Metal concrete in surki mortar	...	Cft.	2,496	
Burnt stone in chunam	...	do	8,601	
Do do superstructure	...	do	9,631	
Cut stone arch work	...	do	208	
Burnt brick in chunam	...	do	338	
Stone for lintels and sills 6" thick (dressed)	...	Sft.	504	
Do for steps 6" and 9" thick dressed	...	do	324	
Cut stone cornice 9" deep and 9" projection	...	Rft.	137	
Parapet complete as per jackey's quarter...	...	do	131	
Stone pillars 1' x 1' x 9 1/2' complete dressed including pillar plate	...	E	7	
Do 1' x 1/2' x 9 1/2' do do do	...	do	6	
Pink painting with colorian to main rooms	...	Sqr.	59-98	
Plastering with chunam interior	...	do	44-46	
Whitewashing excepting main rooms	...	do	44-46	
Pointing with chunam outside	...	do	46-19	
Flooring with square tiles over 6" concrete and cement pointing	...	do	26-00	
Do with stone slabs 3" do do	...	do	3-03	
Weins coating 6" high with glazed tiles complete	...	Sft.	186	
Roofing with Mangalore tiles battens complete	...	Sqr.	39-32	
Do terraced 9" thick	...	do	9-89	
Ridging with cresting	...	Rft.	150	
Teak wood work wrought and put up including wood ceiling complete	...	Cft.	613 1/2	
Doors including frames (4' x 8') half panelled and half glazed	...	Sft.	224	
Do panelled (4' x 8' and 3 1/2' x 6 1/2')	...	do	169	
Do patterned (4' x 8' and 3 1/2' x 6 1/2')	...	do	72	
Windows panelled outside and glazed inside	...	do	280	
Ventilators glazed	...	do	119	
Recess planks 1' apart and 1" thick	...	Cft.	12	
Plank ceiling 1/2" to roof	...	Sqr.	19-13	
Eaves similar to one to Geological Department Mill House	...	Rft.	318	
Holding down bolts 4" deep, 1/2" dia. 65lbs. with anchor plates	...	E.	31	
12" x 12" x 1/4" @ 10lbs. per Sft.	...			
Down pipes zinc	...	do	10	
8" Drains	...	Rft.	300	
Laying on water	...	L.S.	...	
Chimney top arch work, pipe, fire place etc. complete	...	E.	1	
Bamboo matting with outer rind	...	Sqr.	25-36	
Balustrades to verandah's at ends	...	Rft.	16	
Levelling site, etc.	...	L.S.	R. S.	
Finials wooden	...	E.	4	
Cut stone mullians to windows	...	do	2	
Wood mouldings with Cudappa stones over windows	...	Rft.	64	
Dressing jambs of windows	...	do	128	
Painting to doors and windows	...	Sqr.	13-78	
Cement plastering for a width of 4' over the terrace along the line where the main roof water drops.	...	do	4-50	
Total Rs.	...			

The 29th December 1897.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Bangalore division, up to 15th January 1898 for extending the Government Store and Stationery Office and erecting Manager's quarters with out-house, &c. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of March 1899.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's office at Bangalore between the hours of 12 and 4 P. M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer and be accompanied by a statement, in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of rupees two hundred in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for extending the Government Store and Stationery Office and erecting Manager's quarters with out-house, &c.," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with Superintending Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Extending the Government Store and Stationery Office, erecting Manager's quarter, out-house, &c., Bangalore.

Items.	Per.	Rate.	Quantity.	Cost.
		Rs. a. p.		
Dismantling	C. ft.		17-67	
Earthwork (excavation)	C. yds.		254	
Burnt stone in chunam	C. ft.		9,224	
Brick in chunam	Do		8,502	
Do arch work	Do		252	
Burnt stone in mud	Do		739	
Brick in mud	Do		733	
Plastering with chunam	Sqr.		138-36	
Do with mud	Do		6-12	
Cornice 1' deep	R. ft.		1,255	
Do 4" deep	Do		102	
Bengal terrace	Sqr.		49-08	
Flat terrace (pucka)	Do		11-71	
Teakwood work with wood oiling	C. ft.		939-61	
Do battened doors with frame, complete	S. ft.		350	
Do venetian windows with iron bars inside and glazed shutters	Do		284	
Semi-circular glazed heads to doors and windows, complete..	Do		79	
Teakwood battened windows with iron bars, complete	Do		10	
Do ventilators with glazed shutters and iron bars	Do		156	
Do do iron barred without shutters	Do		12	
Do screen complete	Do		222	
Cudappa stone flooring	Sqr.		38-71	
Slab stone flooring	Do		1-72	
Concrete foundation and flooring	C. ft.		1,235	
Flooring with 3" concrete	Sqr.		30-00	
Stone slabs roughly dressed	S. ft.		875	
Pointing with chunam	Sqr.		9-40	
Ornamental parapet wall with brick in chunam 1½' and plastering	R. ft.		452	
Wood oiling to doors and windows	Sqr.		3-84	
Whitewashing interior	Do		98-41	
Color washing exterior	Do		50-39	
Earth filling in basement	C. yds.		23	
Eave boards 9"	R. ft.		122	
Roofing with pot tiles, reepers, nails, &c., complete	Sqr.		4-50	
Painting to doors and windows	Do		3-84	
Straps and bolts for trusses	Lump	sum Rs.	10	
Total				

B. S. VENKATACHARIYAR, Executive Engr.

2 D